



NOTES

1. PRECAST REINFORCED CONCRETE MANHOLE PIPE TO MEET REQUIREMENTS OF ASTM C 478 SPECIFICATIONS WITH INCREASES IN REINFORCEMENT AND WALL THICKNESS TO MEET LOCAL REQUIREMENTS. MINIMUM COMPRESSIVE STRENGTH OF CONCRETE SHALL BE 4,000 PSI AT 28 DAYS.
2. THE DRY WELL SHALL BE CONSTRUCTED BY USING INTERLOCKING PRECAST SECTIONS.
3. THE FINAL DESIGN SHALL BE APPROVED BY THE CITY ENGINEER.

CITY OF CARSON

REVISIONS	DATE	DRY WELL		DRAWN BY:
DATE APPROVED: 8/29/22	RECOMMENDED:	APPROVED:	NO. 703	
SHEET 1 OF 1	CITY ENGINEER	DIRECTOR OF PUBLIC WORKS		